



Utility Engineering Consultants, LLC

Phone : 205.951.3838
FAX : 205.951.3839
WEB : www.uecllc.com

130 Southcrest Drive, Suite 100
Homewood, AL 35209
P.O. Box 19218
Birmingham, Alabama 35219

July 2, 2024

Heflin Water Works and Sewer Board
1219 Almon Street, Suite F
Heflin, Alabama 36264

**RE: ADDENDUM NO. 2
 HEFLIN WATER WORKS AND SEWER BOARD
 WASTEWATER LAGOON UPGRADES
 CWSRF PROJECT NO. CS010452-05 CONTRACT NO. HEF23 076**

All Contractors shall acknowledge receipt of Addendum No.2 for above referenced job by signing and returning this statement by email: ktwymon@uecllc.com or fax to (205) 951-3839.

Contractor: SECI

Received by: Allyson Shipps

Date: 7/2/24



Utility Engineering Consultants, LLC

Phone : 205.951.3838
FAX : 205.951.3839
WEB : www.uecllc.com

130 Southcrest Drive, Suite 100
Homewood, AL 35209
P.O. Box 19218
Birmingham, Alabama 35219

July 2, 2024

Heflin Water Works and Sewer Board
1219 Almon Street, Suite F
Heflin, Alabama 36264

**RE: ADDENDUM NO. 2
HEFLIN WATER WORKS AND SEWER BOARD
WASTEWATER LAGOON UPGRADES
CWSRF PROJECT NO. CS010452-05 CONTRACT NO. HEF23 076**

The changes, modifications and/or additions covered by the set forth in this Addendum No. 2 shall become part of and be incorporated in the Specifications, Contract Documents and Bid Documents for the above referenced Project.

CLARIFICATIONS:

1. Gate valves and check valves can be fusion bonded epoxy valve instead of stainless steel.
2. Zinc coating is not required on the exterior of D.I. Pipe.
3. Drawing 18 The Aerator panel is a distribution panel for the aerators it is new. Delete MCC-1 reference on this page only
4. Drawing 20 the MCC is a replacement MCC for the lagoon, contractor shall need to reconnect all the electrical to new MCC. Unit heaters are new see specs.
5. Aerator 1 is fed from new MCC, the rest from aerator panel. The SCADA panel shall be mounted in effluent pump station.
6. UV disconnects shown on drawing 22 are connections to UV panel from manufacturer.
7. Sheet 23 all equipment shown is existing except for aerators, influent pump control panel, effluent pump control panel, UV, unit heaters, septage station, bar screen and conveyor.

This Addendum No. 2 is for clarifications of the Specifications Documents. Acknowledgment of receipt of Addendum No. 2 shall be noted in the Bid for Unit Price Contracts Section of this contract.

UTILITY ENGINEERING CONSULTANTS, LLC

Dave Bechtel

DB/kt