

CLARIFICATION NO. 3
OF THE CONTRACT DOCUMENTS

Date: September 18, 2023
Project No.: D3592400

for the construction of
**H.C. MORGAN WPCF CLARIFIERS NO. 1 AND NO. 2 WEIRS AND BAFFLES
REPLACEMENT PROJECT**

CITY OF AUBURN, ALABAMA

To All Planholders and/or Prospective Bidders:

The following are issued as clarifications of the Contract Documents for the construction of H.C. Morgan WPCF Clarifiers No. 1 and No. 2 Weirs and Baffles Replacement Project dated September 2023. Clarifications do not change the language of the Contract Documents but instead clarify the language therein:

Questions and Related Answers:

1. Question: Sheet D-02, Note 5, we have assumed no concrete remediation or repair work, please confirm this is correct.

Answer: No concrete remediation or repair work is expected. Any damage to existing concrete incurred during construction of this project shall be repaired.

2. Sheet D-04, V-Notch Weir – Type B, Note 2, we have assumed we will not have to do anything to the top of the existing weir wall, please confirm this is correct.


Answer: This is correct.

3. Sheet D-04, Scum Baffle Detail, Detail 3 of 3, this detail shows bolting the closure angle to the baffle plate in four places, the Scum Baffle Detail, Detail 1 of 3 shows the closure angle being field welded to the baffle plate in two places 6” long. The manufacturer has not said this is required, is this required, if so this will be a considerable amount of money to stitch weld the angles to the plates in approximately 36 locations per clarifier.

Answer: Field stitch welding will not be required.

Please acknowledge receipt of Clarification No. 3 at your earliest convenience.

JACOBS



Whitney Zirkle, P.E.
Project Manager

END OF CLARIFICATION